

STL-100 ~ Low voltage Transformer

FIXTURE SPECIFICATIONS:

Housing Material:

304 Brushed Stainless Steel.

Core:

Fully encapsulated EI Magnetic core

Timer Module:

Integrated Timer Module, Field replaceable, Countdown Timer function- 1, 2, 4, 6, 8-hour durations, Always OFF, Always ON Auto – photocell drives duration Low Voltage photo cell with 25' lead included.

Watts: 100

Wiring:

125° C rated internal wiring.

Electrical specs:

100 watts. 6' – heavy duty power cord 120-volt input, Terminals for output, Terminals for 15' photocell input, Primary thermal protection included, Secondary side magnetic circuit breaker included on / off switch. Hi / Lo Switch – Toggles 12 Volt output on Low, 15 Volt output on Hi

Mounting/ Fasteners:

Keyhole slot, Quick mount bracket. Knockout holes.

Certification:

CETL listed and approved

Dimensions in MM:

