

STL-150 ~ Low voltage Transformer

FIXTURE SPECIFICATIONS:

Housing Material:

304 Brushed Stainless Steel.

Core:

Fully encapsulated EI Magnetic core

Timer Module:

Integrated Timer Module, Field replaceable, Countdown Timer function- 1, 2, 4, 6, 8-hour durations, Always OFF, Always ON Auto – photocell drives duration Low Voltage photocell with 25' lead included.

Watts: 150

Wiring:

125° C rated internal wiring.

Electrical specs:

150 watts. 6' – heavy duty power cord 120-volt input, Terminals for output, Terminals for 15' photocell input, Primary thermal protection included, Secondary side magnetic circuit breaker included on / off switch. Hi / Lo Switch – Toggles 12 Volt output on Low, 15 Volt output on Hi.

Mounting/ Fasteners:

Keyhole slot Quick mount bracket. Knockout holes

Certification:

CETL listed and approved. 5-year warranty.

Dimensions in MM:

